



0

0

0

0

 $\Theta$ 0 0

0

0

0

0

0

0

0 0 0

0

0 0

## **SIGN MOUNTED ON METAL TUBING**

1000 MIN.

CLEAR ZONE

450

OPTION B:

TWO (2) SIGNS

MOUNTED ON

METAL TUBING

450

## SIGN MOUNTED ON UTILITY POST

## NOTES:

- 1. ALL SIGNS SHALL BE MOUNTED ON 'TELESPAR' GALVANIZED PERFORATED TUBING (EXCEPT WHERE CO-USAGE OF EXISTING UTILITY POLES IS POSSIBLE), APPROXIMATE SPACING 500 M TO 700 M. 'TELESPAR' TO BE INSTALLED AS PER MANUFACTURERS SPECIFICATIONS.
- 2. AVOID POLES NEXT TO TREES, VEGETATION OR OTHER VISUAL OBSTRUCTIONS.

SIGN POST:

44 MM PERFORATED

**TELESPAR TUBING** 

ANCHOR SLEEVE:

**57 MM PERFORATED** 

SIGN POST ANCHOR: 51 MM PERFORATED

**TELESPAR TUBING** 

**TELESPAR TUBING** 

- SIGNS TO BE ATTACHED TO TUBING BY 'TELESPAR' DRIVE RIVETS (TL 3806).
- SIGNS TO BE INSTALLED ONTO A UTILITY POLE BY ALUMINUM STRAPPING WITH BUCKLES AND CLIPS.
- IN SITUATIONS WHERE MULTIPLE SIGNS ARE TO BE MOUNTED ON ONE POLE, THE PATHWAY WAYFINDING SIGN SHALL BE MOUNTED ON THE TOP.

**TRAIL** 

- SIGNS TO BE 450 MM X 450 MM OR 450 MM X600 MM IN SIZE.
- ALL MEASUREMENTS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.



PATHWAYS WAYFINDING SIGNAGE INSTALLATION

**9** 

⊢. Z

**MARCH 2015** 

**SERIES 800** 

SITE AMENITIES